

Management of undulators production and commissioning for the European XFEL

Suren Karabekyan

Argonne National Laboratory

October 14th, 2019


European XFEL

Suren Karabekyan, ANL, October 14th, 2019

Outline

- Project overview
- Project management aspects
- Experience
 - Planning
 - Execution
- Lessons learned

Facility overview





Undulator Systems

	SASE1/2	SASE3
λ _u [mm]	40	68
Operational Gap	10-20	10-25
Range [mm]		
K-Range	3.9–1.65	9.3-4
Radiation Wavelength Rang		
@ 17.5 GeV	0.147-0.040	1.22-0.27
@ 14.0 GeV	0.230-0.063	1.90-0.42
@ 12.0 GeV	0.310-0.0828	2.44-0.621
@ 8.5 GeV	0.625-0.171	5.17-1.15
Number of Segments	35	21
System Length [m]	213.5	128.1

European XFEL

Photon Energy Range





Repetition rate: < 27000 pulses/ sec


Undulators Production Project Planning



12 countries are participating in the European XFEL project


- Looking for the possibility of in-kind contribution
- Selection of partners
- Project coordination
 - Laboratory visits, technical discussions
 - Specifications
 - Instructional documentation
 - Meetings organization
 - Weekly videoconferences
 - Preparations for using Electronic Document Management System (EDMS)
 - Documentation process introduction
 - Archiving

Undulators Production Ordering Process Flow



Production Process Flow

European XFEL



Serial Production of Undulator Segments:

External Production in Industry

Mechanical Support Systems















VACUUMSCHMELZE









Magnetic Structuress





Production at European XFEL in Hall 5

New Undulator Segments


3 climatized Magnetic Labs

Assembly Area for Magnetic Structures

Segments waiting for Magnetic

Measurements

Measured and tuned **Segments**



Incoming Magnetic Structures from VAC

Steps @ XFEL.EU:

- **Mounting of magnetic** structures
- **Local Control System** Commissioning
- Magnetic Measurements & **Tuning**
- Documentation. **Preparation for** Installation


Schedule:

- Total Time ≈ 2 Years (starting Oct/12)
- Scheduled End: Oct / End 2014
- → 3 Magnetic Labs needed running in parallel
- 3 Weeks/Undulator

Hall 5 was rapidly filled up. Assembled and tuned undulators were stored in a hall, outside of DESY premises .

Quality Plan - Undulator Segments Process Specification - FAT

- Test of welding seams
- Surface Treatment documentation
- Non-Conformance, Change Management
- Factory Acceptance Test (FAT)
 - Support Frame Quality, App, (Table 1)
 - Support Frame with Drives, (Table 2)
 - Girder Quality, (Tables 3 & 4)
 - Final Test of Support System, (Table 5)
 - Undulator-Checklist: Flawless Operation
- Certificates and Dimensional Control documents
 - Inspection Reports
 - Laser Tracker Reports



European XFEL

Quality Plan - Undulator Segments Process Specification – SAT

- The SAT should demonstrate the full operability of the support structure under full magnetic forces. This includes:
 - Dimensional precision of the girder mounting
 - Precision of the guiding system
 - Angular alignment and distortion of the girders on the basis of the reference surfaces when subject to magnetic forces
- These measurements are a proof of the final state. The following measurements need to be done as a function of the gap:
 - Transverse girder position (z). Max offset: ± 0.25mm
 - Girder inclination on both ends on the Top and bottom girders using a precise frame spirit level
 - ▶ Max. Tilt of a magnet girder without magnet structure: ± 0.11mrad
 - ▶ Max. Tilt of a magnet girder with magnet structure: ± 0.20mrad

ilt nur für die Magnetträger MT

Skizze 1

Quality Plan - Undulator Segments Testing of Control Components

- For the magnetic commissioning of the undulator it was necessary to bring it into the magnetic measurement hutch.
- Control of all undulators introduced to the hutch can be carried out using the same rack
- It was decided to commission the undulator with the assigned control rack.
- During this commissioning, a complete set of tests was carried out.
- The hardware related errors was about 5% of the system



Quality Plan for XFEL Undulator Segments Documentation and Archiving

- EDMS schooling → upload rights of the documents to the companies
- Archiving all documents, protocols, certificates into the EDMS
- Supervising and controlling by the XFEL responsible




SASE 1 - XTD 2 10.10.2019 21:00:04 (CE(S)T)

XFEL Cell Regular SASE 1	Cell01.SA1	Cell02.SA1	Cell03.SA1	Cell04.SA1	Cell05.SA1	Cell06.SA1	Cell07.SA1	Cell08.SA1	Cell09.SA1	Cell10.SA1	Cell11.SA1	Cel
	M.	**										
Undulator U40 XFEL Diagnostics Undulator			X069-K029	X062-K022	X008-N006	X044-K004	X002-K002	X064-K024	X058-K018	X050-K010	X045-K005	
XFEL-Undulatorkammer	XFEL-Undu-Kammer-010	XFEL-Undu-Kammer-035	XFEL-Undu-Kammer-019	XFEL-Undu-Kammer-047	XFEL-Undu-Kammer-062	XFEL-Undu-Kammer-051	XFEL-Undu-Kammer-048	XFEL-Undu-Kammer-058	XFEL-Undu-Kammer-049	XFEL-Undu-Kammer-056	XFEL-Undu-Kammer-061	XFEL-L
Aircoil Big SASE 1+3			0102	0123	0132	0131	0130	0134	0133	0135	0125	
Aircoil Small			0020	0030	0031	0032	0021	0022	0023	0024	0025	
XFEL Intersection Start SASE XFEL Intersection Regular SASE	1084	<u>1024</u>	<u>I015</u>	<u>I017</u>	<u>1085</u>	<u>1079</u>	<u>1060</u>	<u>1088</u>	<u>1063</u>	<u>1076</u>	<u>1057</u>	
Phase Shifter			PS070-I010	PS076-I016	PS063-I003	PS067-I007	PS071-I011	PS068-I008	PS074-I014	PS066-I006	PS085-I025	
BLM: Beam Loss Monitor	XFEL BLM 0069	XFEL BLM 0076	XFEL BLM 0121	XFEL BLM 0086	XFEL BLM 0096	XFEL BLM 0087	XFEL BLM 0077	XFEL BLM 0078	XFEL BLM 0088	XFEL BLM 0099	XFEL BLM 0089	XF
BLM: Beam Loss Monitor	XFEL BLM 0160	XFEL BLM 0081	XFEL BLM 0122	XFEL BLM 0091	XFEL BLM 0097	XFEL BLM 0092	XFEL BLM 0082	XFEL BLM 0083	XFEL BLM 0093	XFEL BLM 0098	XFEL BLM 0094	XF
XQA Quadrupole with Chamber	QA.2241.SA1	QA.2247.SA1	QA.2253.SA1	QA.2259.SA1	QA.2266.SA1	QA.2272.SA1	QA.2278.SA1	QA.2284.SA1	QA.2290.SA1	QA.2296.SA1	QA.2302.SA1	2
XQA Quadrupole Magnet	XQA084	XQA079	XQA016	XQA063	XQA096	XQA060	XQA107	XQA062	XQA061	XQA031	XQA104	
Quadrupole Chamber	FEL VQ3 074	FEL VQ3 057	FEL VQ3 070	FEL VQ3 043	FEL VQ3 067	FEL VQ3 071	FEL VQ3 066	FEL VQ3 052	FEL VQ3 054	FEL VQ3 072	FEL VQ3 050	E
BPM and Pumping Unit	FMB 114 2013 PU	FMB 037 2013 PU	FMB 031 2013 PU	FMB 034 2013 PU	FMB 029 2013 PU	FMB 024 2013 PU	FMB 047 2013 PU	FMB 050 2013 PU	FMB 023 2013 PU	FMB 019 2013 PU	FMB 039 2013 PU	FME
BPME: Beam Position Monitor E	FMB 114 2013	FMB 037 2013	FMB 031 2013	FMB 034 2013	FMB 029 2013	FMB 024 2013	FMB 047 2013	FMB 050 2013	FMB 023 2013	FMB 019 2013	FMB 039 2013	E
Pumping Unit	FEL VU2 022	FEL VU2 001	FEL VU2 031	FEL VU2 034	FEL VU2 029	FEL VU2 024	FEL VU2 009	FEL VU2 010	FEL VU2 075	FEL VU2 019	FEL VU2 002	E
Ion getter pump	301266107	301266109	301266803	301268603	301266110	<u>301268604</u>	301266802	301268605	301268615	301268508	301267603	
Quadrupole Mover	Q032-R029	Q033-R030	Q092-H045	Q093-H046	Q014-R011	Q015-R012	Q037-R034	Q036-R033	Q042-R039	Q043-R040	Q087-H040	
BPM Support	MI47964	MI47911	MI47907	MI47960	MI47963	MI47920	MI47974	MI47971	MI47970	MI47972	MI47969	
I-Section Table	MI47889	MI47829	MI47820	MI47822	MI47890	MI47884	MI47865	MI47893	MI47868	MI47881	MI47862	
Height Adjustment Unit	HeightAdjust-Lot-01	Heig										
Turn Buckle	TurnBuckle-Lot-01	Tur										
Tilt Safety Device	TiltSafety-Lot-01	Till										
I-Section Pedestal	ISecPedestal-Lot-01	ISec										


Quality Plan - Undulator Segments Documentation and Archiving

- All Related Items are linked
- Easy access to the database and all related items using QR code



Intersection

- **Undulator System** Group is responsible for the following components: Quadrupole Mover, Phase Shifter, Air coils, Support basies, Intersection Control Racks,
- 9 companies were producing the intersection
- Factory and Site acceptance tests have been requested



1/39

Quality Plan - Intersection Components In-Kind Contribution Case

- Quadrupole Movers and Intersection Control Racks have been produced in Spain
- Collaborating institute Ciemat
- Ciemat organized the call for tenders in Spain
- For each product three companies were qualified
- Each company produced one prototype
- After the comparison of the prototypes a vendor was selected
- Documentation by Ciemat
 - Technical specification
 - Validation test
 - EPLAN
- Documentation for FAT
- EDMS archiving

European XFEL


Technical Specifications for the Supply of the Intersection Control Racks (ICRs) for the European XFEL

Validation test for the XFEL Intersection Control Rack (ICR)

Cristina Vázguez Vélez 25/07/2012 Draft v.05 C. PLC control signals directly related to motion control... C.2 MOVER DRIVERS CONFIGURATION C.3 PHASE SHIFTER DRIVER CONFIGURATION C.4 AXES BRAKE CONTROL TEST C.5. MOVER AXIS CONTROL TEST C.6 PHASE SHIFTER AXIS CONTROL TEST C.7 SIGNAL INTEGRITY TEST D. Safe stop procedure under Emergency Stop and power failures.... D.1 MOVER AXIS SAFE STOP TEST D.2 PHASE SHIFTER AXIS SAFE STOP TEST APPENDIX A: LVDT Cablibration Assembly Electrical Diagram APPENDIX B: ICR Validation Protocol Tests Checklist. APPENDIX C: EPLAN ICR Electrical Diagram (electronic)...

Quality Plan - Intersection Components In-Kind Contribution Case - SAT

- Air conditioned and thermo stabilized hutch (XFEL)
- Infrastructure, granite stone, requesting hardware (XFEL)
- Supervisory Control And Data Acquisition (SCADA) program was created by Ciemat
- After delivery to XFEL the SAT was organized by Ciemat



ELECTRICAL DIAGRAM
INTERSECTION CONTROL RACK

Quality Plan - Intersection Components In-Kind Contribution Case - EDMS

- Archiving of the documents in EDMS by Ciemat
 - Declaration of CE comformity
 - Manufacture report
 - Calibration report
 - Reception report
 - Validation test report

Reception Report

ICR ID. Ref: 1005-P003

Done	Action	Checking/A
Y	Visual cleanness and integrity (ICR surface)	When action
Y	Check shock sensors integrity	When action
Y	Check cable hoses, feedthrough and grommets integrity	When action
Y	Check external hoses external connectors integrity	When action
Y	Check key operation (if it is the case)	When action
Y	Check door opening/closing	When action
Y	Check door hinge fixations	When action
Y	Visual cleanness and integrity (ICR interior)	When action
Y	Validation report & declaration of conformity attached and OK	When action
Y	Check ICR ID reference on box and all documents attached	ID
Y	Check shock sensors ID on Validation report	ID
Person	Pablo Concha	
Date	12.02.2014	
Sign.	PC	

Hereby declarate that the following equipment has been designed, menufactured and verified according to application Directives.

EQUIPO: EQUIPMENT	1005-P003	
Nº ASUNTO: SUBJECT №	CE 14914	
CLIENTE: CUSTOMER	CIEMAT	
INSTALACIÓN: INSTALLATION	X-FEL EUROPEO	

Pine

DECLARACION DE CONFORMIDAD "CE" DECLARATION OF CONFORMITY "CE"

PINE EQUIPOS ELECTRICOS, S.A. Pol. Ugaldeguren II, Pab.9 - I 48170 ZAMUDIO (VIZCAYA) Declara por la presente que los equipos abajo relacionados han side diseñados, fabricados y verificados de acuerdo a las Directivas de aplicación.

DIRECTIVAS APLICADAS:

ZAMUDIO A 20 DE ENERO DE 2014

Contact: (+34) 914962561

Calibration Report ICR ID. Ref: 1005-P003 Contact: (+34) 944520565 A1 POWER SUPPLY CALIBRATION rint ICR ID reference on componen

A2 POWER SUPPLY CALIBRATION N1 LVTD DRIVER CALIBRATION djust N1 to 12mA (Ch.1 disconnected) en action done Adjust micrometer position for 12mA (Ch.1 connected) Adjust V1 potentiometer to 16mA (1mm displacement) Adjust N2 to 12mA (Ch.2 disconnected) A1 (mm) When action done Adjust micrometer position for 12mA (Ch.2 connected)
Adjust V2 potentiometer to 16mA (1mm displacement)

ICR ID. Ref: 1005-P003 Switch on PC CIEMAT Swith on Emergency Stop Button (EMS) Platform and rearm EMS Buttor Connect W02 to EMS Platform

onnect W03 Ethernet Cable to Beckhoff PLC

"Validation_ICR.exe" on PC CIEMAT

nnect W05 to Phase Shifter sarm all MCB protections

heck Mover is attached to granite table ape cables W04-W07 together & connect W04 to I-onnect W05 to Mover

Validation Report

en action done earm MCB protections in this order: Q1,Q2, F1, F2, F3, F4 & F5 en action done en action done

European XFEL

When action done

Quality Plan - Undulator System Undulator system test setup

- The system is controlled by a central control node (CCN), which is located about 1 km away from the undulator system
- CCN communicates with the undulator cells over optical fibers
- Media converter racks are used to convert signals from copper carriers to optical fiber carriers and vice versa



- It was obvious that all components should be tested before installation in the tunnel
- An undulator system test setup with 4 cells was built in the undulator hall
- It was used for developing the global control system software three years ahead of the installation of the system in the tunnel.

Lessons learned

- Beckhoff control system integration in companies
- Wiring on the undulator frame
- Male types plug for the phase shifter stepping motor
- Cabling issues in the tunnel
- Every piece of hardware must be tested before installation in the tunnel