



Europe/Berlin timezone



European XFEL Users' Meeting 2011 -
HASYLAB Users' Meeting 2011


26-28 January 2011 *DESY, Notkestr. 85, 22607
Hamburg, Germany*

The Electron Accelerator of the European XFEL


Hans Weise / DESY




The First Tunnel



480 m within the First two Months



- Starting excavation of main linac tunnel beginning of 2011
- Arrival at DESY Bahrenfeld (injector) in summer 2011



July 2010
Starting excavation of tunnel sections between Schenefeld and Osdorfer Born (XDT1, XTD2)

Beginning of 2011
Starting excavation of main tunnel between Osdorfer Born and DESY-Bahrenfeld (XTL)

Summer 2011
Arrival at DESY-Bahrenfeld, disassembly

TBM 1



Fall 2010
Arrival of TBM 2 at site Schenefeld

Beginning of 2011
Starting excavation (XTD9, XTD10, XTD4, ...)

Summer 2012
Arrival at final shaft, disassembly


TBM 2

- A - XTD9 ... 544 m
- B - XTD10 ... 220 m
- C - XTD4 ... 300 m
- D - XTD8 ... 361 m
- E - XTD7 ... 141 m
- F - XTD5 ... 200 m
- G - XTD3 ... 267 m
- H - XTD6 ... 660 m




Sequence of excavations (TBM 2)
Boring direction >>>


The Injector Building



Accelerator Complex Start-up Version





100 accelerator modules




800 accelerating cavities
1.3 GHz / 23.6 MV/m





25 RF stations
5.2 MW each




Accelerator Complex Start-up Version




	Baseline
Electron beam energy	17.5 GeV
Bunch charge	1 nC
Peak current	5 kA
Slice emittance	< 1.4 mm mrad
Slice energy spread	1.5 MeV
Shortest SASE wavelength	0.1 nm
Pulse repetition rate	10 Hz
Bunches per pulse	3000




Accelerator Complex with New Parameter Set




	Baseline	New Parameter Set
Electron beam energy	17.5 GeV	14 GeV
Bunch charge	1 nC	0.02 - 1 nC
Peak current	5 kA	2 - 5 kA
Slice emittance	< 1.4 mm mrad	0.4 - 1.0 mm mrad
Slice energy spread	1.5 MeV	4 - 2 MeV
Shortest SASE wavelength	0.1 nm	0.05 nm
Pulse repetition rate	10 Hz	10 Hz
Bunches per pulse	3000	2700





0.25 nC


Saturation after 65 m



Courtesy P. Emma, H.D. Nuhn, et al.

20 pC




X-ray pulse should be < 10 fs (no measurement possible yet)




Consequences for the European XFEL

- SASE with electron beam parameters as simulated ⇒ safety margins can be reduced
- Operation at low charges with strong compression feasible ⇒ include scheme from beginning


DESY PITZ Results on Emittance



Measured projected emittance versus bunch charge




Possible Shortening of the LINAC




- Improved beam quality **gives possibility to save money** by shortening the linac while keeping the baseline performance.
- Extensive simulations support the new parameter set.
- **BUT:**
 - Reduced safety margin
 - Reduced photon energy reach
 - Makes eventual later conversion to cw more expensive
- Proposal to XFEL Council $E_{\text{final}} = 17.5 \text{ GeV} \rightarrow 14 \text{ GeV}$
- All other accelerator system still laid out for $>17.5 \text{ GeV}$
- Missing modules will be substituted by simple warm beamline
 - approx. 6 additional quadrupoles are required
 - additional 240 m of 40.5 mm beam-pipe

Accelerator Complex with New Parameters





80 accelerator modules




640 accelerating cavities
1.3 GHz / 24.3 MV/m




20 RF stations
5.2 MW each




Cavities





- **Research Instruments and E. Zanon** were contracted to produce each
 - **4+4 pre-series cavities**
 - **280 XFEL type series cavities**
 - **12 HiGrade cavities**, first used for quality assurance, later available for further investigations & treatments (high gradient R&D towards ILC)
 - **Nb / NbTi to be supplied by DESY**
 - Production precisely following the specifications which also include the exact definition of infrastructure to be used
 - Final treatment after bulk electro-polishing (EP): EP for RI / flash BCP for Z
 - **No performance guaranty by the vendors**, i.e. the risk of unexpected low gradient or field emission is with DESY (responsibility for re-treatment); goal: average usable XFEL gradient 24.3 MV/m
 - **Additional 80 cavities** are ordered as an option to be placed after the evaluation of the successful start of the series production
 - **First series cavities beginning of 2012**; all cavities to be delivered within two years; He-vessels for RI cavities to be supplied by DESY
 - Both contracts have a volume of almost 25 M€ each

Cavity - Kick-off Meetings




research
instruments

Kick-off meeting at DESY XFEL cavity production


Michael Peiniger, Hanspeter Vogel, Michael Pelebin,
Helmuth Röhrig, Stefan Bauer

RI Research Instruments GmbH
Friedrich-Ebert-Str. 1
51429 Bergisch Gladbach

Cavity Surface Treatment – Based on DESY Experience





- Two schemes for the final surface treatment (*Final EP* and *BCP Flash*) were studied with cavities from two different vendors.
- The preparation strategy to go for a final treatment with the cavity already welded into the He-vessel was investigated.



Results are:


- yield curves for the different schemes
- yield curves for the different vendors
- a preparation strategy allowing two different final treatments
- Some tooling will come from DESY
- DESY procedures and experience described very much in detail in the CFT
- Specification will be made available to the SRF community around end of 2010.

RF Measurement and Field Flatness Tuning using DESY-provided Tools



- Both machines ready to be used at the companies (CE certified).
- Machines can be operated by Non-RF-Experts.
- **Considerably shorter measurement / tuning time.**
- Automation and documentation guaranteed.

Transport Solution for XFEL Cavities



RI Germany




Z Italy



DESY Germany





IRFU /CEA France






- DESY takes care of installation / dismantling of cavities into / from test insert
- Transport to CEA in transport boxes as well

Transport Simulation



- Sweep (0.1 g), Transport simulation (up to 2 g) 1200 km with Shocks applied up to 6 g
- Final test done without external dampers, only internal foam elements.





■ Eigen frequencies

■ Field flatness

■ Cavity gradient

XFEL RF Power Coupler – LAL Orsay Contribution



■ *TTF3 coupler type*




■ **LAL Orsay** has taken over the responsibility for the XFEL RF power coupler production.

■ **Conditioning** of the couplers will take place at LAL Orsay.

■ The **coupler interlock system** was developed and will be **contributed by DESY**.


■ **Contract for the production of 640 couplers** recently placed at a consortium of **THALES & Research Instruments**.
Kick-off Meeting on Sep.13, 2010.

XFEL RF Power Coupler – Conditioning at LAL





- Conditioning rate of **8 couplers per week** with max. 5 MW RF power.
- Either pairs (4 x 2 couplers) or units of 4 couplers (under study).
- Schedule integrated in overall project schedule.
- Direct delivery to assembly site at CE Saclay.

Detailed Planning of required LAL Clean room




PXFEL – Three Modules from Different Vendors




- Three XFEL prototype modules were built and tested over the last two years.
- Assembly procedures improved during assembly training with new teams.


PXFEL – Modules from Different Vendors



- PXFEL1 is a great module above 30 MV/m; cryostat contributed by IHEP Beijing.
- After string / module installation the **gradient reduction is only 5%**.
- Now operated at FLASH with an average gradient of **30 MV/m using the XFEL waveguide distribution.**




■ PXFEL1




Institute of High Energy Physics
Chinese Academy of Sciences

PXFEL – Modules from Different Vendors




- PXFEL1 is a great module above 30 MV/m; cryostat contributed by IHEP Beijing.
- After string / module installation the **gradient reduction is only 5%**.
- Now operated at FLASH with an average gradient of **30 MV/m using the XFEL waveguide distribution.**

- PXFEL2: av.gradient 29.6 MV/m
- **BUT:** 3rd cavity dropped from 27 down to 16 MV/m and neighboring cavities show field emission.
- Looks like an assembly problem but no hint in the reports. **Module was used for string & module assembly training.** Investigations ongoing.



■ PXFEL1




Institute of High Energy Physics
Chinese Academy of Sciences

■ PXFEL2



PXFEL – Modules from Different Vendors



- PXFEL1 is a great module above 30 MV/m; cryostat contributed by IHEP Beijing.

- After string / module installation the **gradient reduction is only 5%**.

- Now operated at FLASH with an average gradient of **30 MV/m using the XFEL waveguide distribution**.

- Module PXFEL3 successfully **tested**.

- **Cryogenic losses & gradients are ok.**

- Result: XFEL module performance reached although again one problematic cavity.


- **Improved current leads** were used for sc quadrupole magnets.

- PXFEL2: av.gradient 29.6 MV/m

- **BUT:** 3rd cavity dropped from 27 down to 16 MV/m and neighboring cavities show field emission.

- Looks like an assembly problem but no hint in the reports. **Module was used for string & module assembly training.** Investigations ongoing.

- PXFEL1



Institute of High Energy Physics
Chinese Academy of Sciences


- PXFEL2



- PXFEL3

THALES

PXFEL – Call For Tender




- All PXFEL cryostats seem to be acceptable. We have seen a **successful technology transfer**.
- Together with E. Zanon who has produced all the previous cryostats we now have **four experienced vendors**.
- DESY has published the Call for Tender, **contracts to be placed in the next weeks**.



Institute of High Energy Physics
Chinese Academy of Sciences



Cavity String & Module Assembly





- Using experience gained at DESY and results of industrial studies, the assembly facility for all XFEL modules will be set up at the CEA-Saclay site.

- CEA (IRFU), CIEMAT, DESY, INFN-Milano, LAL Orsay, Swierk take the responsibility for the cold linac.




Module Assembly - Workstations




irfu
cea
saclay

String Assembly - Workstations





■ All cavities with He tank, the coupler cold parts and the quadrupole-BPM units will be cleaned and dried externally before entering ISO4 area

Infrastructure for Cavity String Assembly




irfu
cea
saclay

Infrastructure for Cavity String Assembly



irfu
cea
saclay

Module Assembly Halls at CE Saclay



■ Three Assembly Halls and Services (offices, dressing rooms, warehouse, central courtyard, etc...) were under rehabilitation:

■ Hall n° 1 is ready

Roll-out Area (RO-WS1, RO-WS2)

Alignment Area (AL-WS1, AL-WS2)

■ Hall n° 2 is ready

Cantilever Area (CA-WS1)


Coupler Area (CO-WS1, CO-WS2)

+ offices and warehouse


■ Hall n° 3 is ready

Shipment Area (SH-WS1, SH-WS2)

Assembly Hall and Services ready since April 2010
Central courtyard re-surfaced in June 2010.



Refurbished DESY Clean Room






- State-of-the-art
- Now used for assembly training
- Later available for repair work

- Increased ISO4 assembly area
- Chemistry and ultra sound infrastructure now in ISO6/5 instead of ISO7/6
- New rotational clean room airlock

- Two independent air systems
- Improved energy balance

Many further In-kind Contributions to the Accelerator Complex



irfu
cea
saclay



Wroclaw University of Technology




PAUL SCHERRER INSTITUT
PSI



Institute of High Energy Physics
Chinese Academy of Sciences





■ RF system

klystrons, modulators, pulse transformers waveguide
assembly & testing, overall coordination

■ LLRF complete system

■ Accelerator **Cryomodules**

Cold masses for Cryomodules (33 pieces)

■ Superconducting cavities

50% of cavities; 100% Nb/NbTi


■ Power couplers

coupler interlock


■ HOM couplers


overall coordination





- **Frequency Tuner**
- **Cold vacuum** (approx. 75%)
- **Cavity string assembly** (approx. 20%)
- **AMTF cryogenics** (approx. 60%)
- **Cold Magnets**
 - magnet testing & current leads
- **Warm Magnets**
 - overall coordination
- **Cryogenics for Linac** (approx. 2/3)
- **Injector**
 - overall coordination and approx. 80% of hardware





■ Bunch Compressor Lattice

Beam Optics Design & Beam Distribution Kickers

■ BPM system (approx. 50%)

■ Special Beam Diagnostics (approx. 75%)

■ Warm vacuum (approx. 80%)



■ Beam dumps (approx. 25%)

■ FEL Concepts


■ Control System

■ Operability

■ Survey / Alignment




DESY In-kind Contributions



- Installation
- Utilities
- Radiation safety
- General safety
- Personnel interlock
- EMC
- Information & Process Support
- AMTF Hall
- 3.9 GHz system (approx. 2/3)



Saclay In-kind Contributions




irfu
cea
saclay


- cavity strings assembly
- cryomodules assembly
- BPMs system




Village XFEL

MONTAGE CRYOSTATING SPIRAL 2








- Power couplers
- procurement
- RF conditioning




INFN In-kind Contributions



- Nb cavities (50%)
- Cold masses for Cryomodules (25%)
- 3.9 GHz accelerator module





Polish In-kind Contributions






Wrocław University of Technology





- **HOM couplers & absorbers**
- **Transfer lines for AMTF**
- **Tests of Nb cavities**
- **Tests of cryomodules in AMTF**
- **Tests of Cold magnets**




Russian “In-kind” Contributions



- **Cryogenics** for Linac
- **Beam dump**
- **Beam diagnostics**
- **Warm magnets**
- Connector module for Klystrons
- quadrupole magnets type XQA
- **Cold vacuum**
- Warm vacuum
- cryomodule test benches for AMTF
- Power supplies for Utilities
- **Transverse Deflecting Structures**





- Superconducting magnets
- Power supplies






- Laser heater system for injector
- Timing & synchronization system + configuration management




- BPM electronics
- Intra-bunch-train Feedback System IBFB

Many Contributions to the Accelerator Complex




Wrocław University of Technology



Institute of High Energy Physics
Chinese Academy of Sciences






With One Common Goal:




Gantt Chart


33			
34	WP3/9 out PM in	string and module assembly training	200 days
35		initial training of new assembly teams	4 wk
36		1st dis- and re-assembly of prototype modu	8 wk
37		CMTB test of re-assembled prototype #1	4 wk
38		2nd dis- and re-assembly of prototype modu	8 wk
39		CMTB test of re-assembled prototype #1	4 wk
40		prototype	
41		prototype	
42		prototype	
43		prototype	
44			
45			
46			
47	WP09 out WP03 in	first pre-series string ready	
48	WP03 out PM in	pre-series module #2	
49	WP09 out WP03 in	second pre-series string ready	
50	WP03 out PM in	pre-series module #3	
51	WP09 out WP03 in	third pre-series string ready	
52		start CMTB module testing	
56			



Finish installation in time.



- So far “in time” has been “in 2014”.
- We are currently crossing the end of the year... can we avoid this?



■ The end